




Coastal
The Energy People

November 24, 1999



State of Utah
Division of Oil & Gas, and Mining
1594 West North Tempole, suite 1210
P.O. Box 145801
Salt Lake City, UT 84114-5801

ATTENTION: Lisha Cordova

Dear Lisha:

Enclosed are the original and two copies of the Application for Permit to Drill for the Hall #31-134, Hall #30-144, Hall #31-130, and the Hall #31-143. Onsite request & Arch Reports to be submitted as soon as the become available.

If you have questions or need additional information, please do not hesitate to call, (435) 781-7023.

Sincerely,

Katy Dow
Environmental Secretary

cc w/ encl: File

Coastal Oil & Gas Corporation

A SUBSIDIARY OF THE COASTAL CORPORATION
1368 S 1200 E • P.O. BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1A. Type of Work

DRILL ☒DEEPEN ☐

B. Type of Well

OIL ☐GAS ☒

OTHER:

SINGLE ZONE ☐MULTIPLE ZONE ☐

2. Name of Operator:

Coastal Oil & Gas Corporation

3. Address and Telephone Number:

P.O. Box 1148, Vernal UT 84078

(435)-781-7023

4. Location of Well (Footages)

At surface:

NWNE

At proposed proding zone:

705' FNL & 2150' FEL

14. Distance in miles and direction from nearest town or post office:

10 miles to Ouray, Utah

15. Distance to nearest property or lease line (feet):

705'

16. Number of acres in lease:

441.31

17. Number of acres assigned to this well:

239.17

18. Distance to nearest well, drilling, completed, or applied for, on this lease (feet):

Refer to Topo "C"

19. Proposed Depth:

11500'

20. Rotary or cable tools:

Rotary

21. Elevations (show whether DR, RT, GR, etc.):

4720.5' GR

22. Approximate date work will start:

Upon Approval

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	9 5/8"	36#	2500'	740 sx
8 3/4"	5 1/2"	17#, 5-95	11300'	2040 sx
		P-110*		
		CRK		

DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

Per CC 1-6-00 (RJR)

Coastal Oil & Gas Corporation is considered to be the operator of the subject well.
Coastal Oil & Gas Corporation agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.
Bond coverage pursuant to 43 CFR 3104 for the lease activities is being provided by Coastal Oil & Gas Corporation Bond #102103, BLM Nationwide Bond #U-605382-9, and BIA Nationwide Bond #144066-A.

(Fee Bond U6053821)

24.

Cheryl Cameron

Title: Environmental Analyst

Date: 11/23/99

(This space for State use only)

API Number Assigned:

43042-33427

Approval:

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 2/3/00

By: [Signature]

(See Instructions on Reverse Side)

NOV 26 1999

DIV. OF OIL, GAS & MINING


T8S, R22E, S.L.B.&M.

COASTAL OIL & GAS CORP.

Well location, HALL #31-130, Located as shown in the NW 1/4 NE 1/4 of Section 31, T8S, R22E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT THE NORTHEAST CORNER OF SECTION 31, T8S, R22E, S.L.B.&M. TAKEN FROM THE RED WASH SW QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4724 FEET.




CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert L. McKay
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 10-28-99	DATE DRAWN: 11-02-99
PARTY J.F. J.J. D.R.B.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE COASTAL OIL & GAS CORP.	



LEGEND:


- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

LATITUDE = 40°05'05"
 LONGITUDE = 109°28'49"

COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

COMPANY NAME	Coastal Oil & Gas Corporation		DATE	11/5/99
WELL NAME	Hall #31-130		TD	11,300' MD/TVD
FIELD	Ouray	COUNTY Uintah	STATE Utah	ELEVATION 4,740' KB
SURFACE LOCATION	750' FNL & 2,150' FEL Sec 31, T8S-R22E		BHL Straight Hole	
OBJECTIVE ZONE(S)	Green River, Wasatch, Mesaverde, Castlegate			
ADDITIONAL INFO				



	DESIGN FACTORS						
	SIZE	INTERVAL	WT.	GR.	CPLG.	BURST	TENSION
CONDUCTOR	14"	0-40'					
SURFACE	9-5/8"	0-2,500'	36#	K-55	STC	2.53	1.73
PRODUCTION	5-1/2"	0-TD	17#	S-95/P-110	LTC	SPECIFIED BY PROD DEPT	
TUBING							


Cement Program

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	0-2,000'	Lite + 2% CaCl2 + 0.25 lb/sk Flocele	520	50%	12.70	1.82
	TAIL	2,000'-2,500'	Class G + 2% CaCl2 + 0.25 lb/sk Flocele	220	50%	15.60	1.19
PRODUCTION	LEAD	0-5,000' (5,000')	Lead + 0.6% Econolite + 0.25 lb/sk Flocele + 0.2% FWCA + 10 lb/sk Gilsonite + 16% Gel + 1% HR-7 + 3% KCl	420	25%	11.00	3.80
	TAIL	5,000'-11,300' (6,300')	50/50 Poz +0.25 lb/sk Flocele + 0.6% HALAD-322 + 2% Gel + 2% MicroBond HT + 5% Salt	1,620	25%	14.35	1.24

Float Equipment & Centralizers

SURFACE	Float shoe, 1 jt, float collar. Centralize first 3 joints & every fourth joint to surface. Thread lock FE & casing up to & including pin end of first joint above FC.
PRODUCTION	Float shoe, 2 jts, float collar. Centralize first 3 joints & every other joint across pay zones. Thread lock FE & casing up to & including pin end of first joint above FC.

Wellhead Equipment

	TREE	2-1/16" 10M
	TUBING HEAD	11" 5M X 7-1/16" 10M
	CASING SPOOL	
	CASING SPOOL	
	CASING HEAD	9-5/8" SOW X 11" 5M

COASTAL OIL & GAS CORPORATION
Drilling Program

Bit Program

Rock Bit & PDC Bit Program

Jan-06-00 04:03pm From-COASTAL OIL AND GAS DOWNSTAIRS SECRETARY +4357894436 T-402 P.04/04 F-896

INTERVAL	BIT MFG & MODEL	GPM	SERIAL	VALVES	COMMENTS
Surface Hole	174"	Various	Air		
SC - Top of Wasatch	8-3/4"	Various	500-400		(No air below surf csg)
Wasatch	8-3/4"	Various (PDC)	500-400	0.5 TFA	
Mesaverde/Castlegate	8-3/4"	Various	450-350		

GEOLOGICAL DATA

LOGGING:

Depth	Log Type
SC - TD	Platform Express

MUD LOGGER:	2,500' - TD
SAMPLES:	As per Geology
CORING:	SWC's at selective intervals possible.
DST:	None Anticipated

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER LOSS	VISCOSITY	TREATMENT
0-2,500'	Air/Mist/ Aerated Water	NA	NA		KCL
2,500'-TD	Water/Mud	8.5-11.0	NC - <10	30-45	KCL, Gel, LCM, Polymer

ADDITIONAL INFORMATION

Test casing head to 1,000 psi after installing. Test surface casing to 1,500 psi prior to drilling out.
BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.
Run Totco survey every 500' from surface casing shoe to TD. Maximum allowable hole angle is 5 degrees.

PROJECT ENGINEER:	Blaine Yeary
PROJECT MANAGER:	Tom Young

DATE:	
DATE:	

HALL #31-130
NW/NE, SECTION 31-T8S-R22E
UINTAH COUNTY, UTAH
LEASE NUMBER: FEE

ONSHORE ORDER NO. 1
COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

1. **Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
KB	4740'
Green River	2050'
Wasatch	5300'
Mesaverde	8050'
Castlegate	10325'
Total Depth	11300'

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Oil/Gas	Green River	2050'
	Wasatch	5300'
	Mesaverde	8050'
	Castlegate	10325'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment:** (Schematic Attached)

The BOP stack will consist of one 11" 5,000 psi annular BOP 11" 5,000 psi double ram, and one 11' drilling spool. The lower ram will contain pipe rams, and the upper ram will contain blind rams.

The choke and kill lines and the choke manifold will have a 5,000 psi minimum pressure.

The BOPE and related equipment will meet the requirements of the 5M system.

4. **Proposed Casing & Cementing Program:**

<i>SURFACE CASING</i>	<i>Depth</i>	<i>Hole Size</i>	<i>Csg Size</i>	<i>Wt/Ft</i>	<i>Grade</i>	<i>Type</i>
	0-2500'	11" or 12 1/4"	9 5/8"	36#	K-55	ST&C

<i>Surface Casing</i>	<i>Fill</i>	<i>Type & Amount</i>
2000'-2500'	2500'	Lead: 520 sx, Lite + 2% Ca Cl + 0.25 Ib/sx Flocele 12.7 ppg 1.82 cf/sx (Cmt will be circulated to surface, about 50% excess) Tail: 220 sx Class G + 2% CaCl ₂ + 0.25 Ib/sx Flocele 15.6 ppg 1.19 cf/sx
<i>Production Casing</i>	<i>Type & Amount</i>	
0-5000'	Lead: 420 sx lead + 0.6% Econolite + 0.25 Ib/sx Flocele + 0.2% FWCA + 10 Ib/sx Gilsonite + 16% Gel + 1% HR-7 + 3% Kcl 11 ppg 3.80 cf/sx	
5000'-11,300'	Tail: 1620 sx 50/50 Poz, + 0.25 Ib/sx Flocele + 0.6% HALAD-322 + 2% Gel + 2% MicroBond HT + 5% Salt 14.35 ppg 1.24 cf/sx	

5. Drilling Fluids Program:

<u>Depth</u>	<u>Type</u>	<u>Mud Wt.</u>
0-2500'	Air/Mist/Aerated Water	N/A
2500-TD	Water Mud	8.5-11.0

6. Evaluation Program

<u>Depth</u>	<u>Log Type</u>
SC-TD	DLL/Cal/SP/GR
2500'-TD	Neutron Destiny/GR
Optional	Sonic
Various	SWC's

7. Abnormal Conditions:

Maximum anticipated bottomhole pressure approximately equals 4,600 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 2,070 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

**Hall #31-130
NW/NE, SECTION 31 -T8S-R22E
UINTAH COUNTY, UTAH
FEE**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

To reach the Hall #31-130 location - Proceed in a Westerly direction from Vernal, Utah along U.S. Highway 40 approximately 14.0 miles to the junction of State Highway 88; exit left and proceed in a Southerly direction approximately 17.0 miles to Ouray, Utah; proceed in a Southerly direction approximately 0.3 miles on the Seep Ridge road to the junction of this road and an existing road to the East; turn left and proceed in an Easterly direction approximately 3.4 miles to the junction of this road and an existing road to the Northeast; turn left proceed in a Northeasterly direction approximately 0.7 miles to the junction of this road and an existing road to the East; proceed in an Easterly then Northeasterly then Southeasterly direction approximately 4.4 miles to the junction of this road and an existing road to the Southeast; turn right and proceed in a Southeasterly direction approximately 0.4 miles to the junction of this road and existing road to the Southeast; proceed in a Southeasterly direction approximately 0.8 miles to the junction of this road and an existing road to the East; proceed in an Easterly then Southeasterly direction approximately 0.5 miles to the junction of this road and an existing road to the Northeast; turn left and proceed in a Northeasterly then Northerly direction approximately 0.8 miles to the beginning of the proposed access for #31-131 to the east; follow road flags in an Easterly direction approximately 0.3 miles to the beginning of the proposed access to the north; follow road flags in northerly direction approximately 0.2 miles to the proposed location.

Total distance from Vernal, Utah to the proposed well location is approximately 42.8 miles.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

Improvements to existing access roads shall be determined at the on-site inspection.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet, ***unless modified at the on-site inspection.*** Appropriate water control will be installed to control erosion.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges;

gates, cattle guards, fence cuts, or modifications to existing facilities shall be determined at the on-site.

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing & Proposed Facilities:**

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Desert Brown, Munsell standard color number 10 YR 6/3.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

The proposed pipeline will leave the well pad in a Southerly direction for an approximate distance of 900' to tie into the proposed pipeline at the #31-131 location. Please see Topo Map D.

5. **Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. **Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids. *The need for a reserve pit liner will be determined at the on-site inspection.*

If a plastic reinforced liner is used, it will be a minimum of 12 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

8. **Ancillary Facilities:**

None are anticipated.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s). ***This section is subject to modification as a result of the on-site inspection.***

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

If it is determined that a pit liner will be used at the on-site inspection, the reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **Plans for Reclamation of the Surface:**

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic, nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final

reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. Surface Ownership:

Lynn S. Hall
% Fred Riding
2256 No. 2500 W.
Vernal, UT 84078

12. Other Information:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey was conducted by Montgomery Archaeological Consultants.

13. Lessee's or Operators's Representative & Certification:


Cheryl Cameron
Environmental Analyst
Coastal Oil & Gas Corporation
P.O. Box 1148
Vernal, UT 84078
(435) 781-7023

Tom Young
Drilling Manager
Coastal Oil & Gas Corporation
9 Greenway Plaza, Suite 2770
Houston, TX 77046
(713) 418-4156

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.


The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Cheryl Cameron

11/23/99

Date



LEGEND:

⊙ PROPOSED LOCATION



COASTAL OIL & GAS CORP.

HALL #31-130
SECTION 31, T8S, R22E, S.L.B.&M.
705' FNL 2150' FEL




Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

10 **29** **99**
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: J.L.G. REVISED: 9-16-99

A
TOPO



LEGEND:

--- PROPOSED ACCESS ROAD
 --- EXISTING ROAD


COASTAL OIL & GAS CORP.

HALL #31-130
SECTION 31, T8S, R22E, S.L.B.&M.
705' FNL 2150' FEL

U E L S **Uintah Engineering & Land Surveying**
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC **10 29 99**
MAP **MONTH DAY YEAR**
 SCALE: 1" = 2000' DRAWN BY: J.L.G. REVISED: 00-00-00

B
TOPO



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

COASTAL OIL & GAS CORP.

HALL #31-130
SECTION 31, T8S, R22E, S.L.B.&M.
705' FNL 2150' FEL




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP
10/29/99
MONTH DAY YEAR
SCALE: 1" = 2000' DRAWN BY: J.L.G. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 900' +/-

LEGEND:

- — — — — EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- PROPOSED ACCESS



COASTAL OIL & GAS CORP.

HALL #31-130
SECTION 31, T8S, R22E, S.L.B.&M.
705' FNL 2150' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

10 29 99
 MONTH DAY YEAR

SCALE: 1"=1000' DRAWN BY: J.L.G. REVISED: 00-00-00

D
 TOPO

UINTAH ENGINEERING & LAND SURVEYING
86 So. 200 East • Vernal, Utah 84078 • (435) 789-1017


COASTAL OIL & GAS CORP.

TYPICAL CROSS SECTIONS FOR

HALL #31-130

SECTION 31, T8S, R22E, S.L.B.&M.

705' FNL 2150' FEL



DATE: 11-02-99

Drawn By: D.R.B.




FIGURE #2



APPROXIMATE YARDAGES

CUT		
(6") Topsoil Stripping	=	1,140 Cu. Yds.
Remaining Location	=	2,620 Cu. Yds.
TOTAL CUT	=	3,760 CU.YDS.
FILL	=	710 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	=	3,010 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	2,480 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	530 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

CHOKING STACK AND CHOKING MANIFOLD SYSTEM



Coastal Oil & Gas Corporation
A SUBSIDIARY OF THE COASTAL CORPORATION
The Energy People

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 11/26/1999

API NO. ASSIGNED: 43-047-33427

WELL NAME: Hall
~~GURAY~~ 31-130
OPERATOR: COASTAL OIL & GAS CORP (N0230)
CONTACT: CHERYL CAMERON

PHONE NUMBER: 435-781-7023

PROPOSED LOCATION:

NWNE 31 080S 220E
SURFACE: 0705 FNL 2150 FEL
BOTTOM: 0705 FNL 2150 FEL
UINTAH
NATURAL BUTTES (630)

LEASE TYPE: 4-Fee
LEASE NUMBER: FEE
SURFACE OWNER: 4-Fee

PROPOSED FORMATION: CSLGT

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	R. M.	1-6-00
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[4]
(No. 46053821)
☒ Potash (Y/N)
☒ Oil Shale (Y/N) *190 - 5 (B)
☒ Water Permit
(No. 43-8496)
☒ RDCC Review (Y/N)
(Date: _____)
☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

____ R649-2-3. Unit _____
____ R649-3-2. General
Siting: _____
____ R649-3-3. Exception
☒ Drilling Unit
Board Cause No: 173-13 (8/320)
Eff Date: 3-24-99
Siting: 400' fr. Dr. Unit Boundary E. 720' between wells
____ R649-3-11. Directional Drill

COMMENTS: Need Presite. (Conducted 12-20-99)

STIPULATIONS: ① STATEMENT OF BASIS




Division of Oil, Gas & Mining

OPERATOR: COASTAL OIL & GAS CORP. (N0230)

FIELD: NATURAL BUTTES (630)

SEC. 30 & 31, TWP 8 S, RNG 22 E

COUNTY: UINTAH UNIT: NONE, CAUSE: NONE



PREPARED
DATE: 2-DEC-1999

Division of Oil, Gas and Mining
Application for Permit to Drill
Statement of Basis

Operator Name: COASTAL OIL & GAS CORP.

Well Name & Number: HALL 31-130

API Number: 43-047-33427

Location: 1/4, 1/4 NW/NE Sec. 31 T. 8S R. 22E

Geology/Ground Water:

The depth to moderately saline water at this location is estimated to be between 200 and 300 feet. The near surface geology of this area consists of interbedded sandstones and shales of the Uinta Formation. The sands of the Uinta are generally lenticular and discontinuous and would not constitute an extensive aquifer. The proposed casing and cement program should adequately protect any potential underground sources of water.

Reviewer: D. jarvis

Date: 01-04-2000

Surface:

The pre-drill investigation of the surface was performed on 12/20/99. Surface owners are David and Lynn Hall. Both Mr. Halls attended this investigation. Both told me that they had no specific concerns concerning the construction of this location or the drilling of this well, but a landowner agreement had not been signed. Site is a legal location per general state siting rule. This site appears to be the best spot for a location in the immediate area. Production equipment for this well will be on a co-mingle battery located 0.5 miles to the southwest on land also owned by the Halls.

Reviewer: David W. Hackford

Date: 12/21/99

Well name:

1-00 Coastal Hall 31-130Operator: **Coastal**String type: **Surface**

Project ID:

43-047-33427

Location: **Uintah County****Design parameters:****Collapse**Mud weight: 8.330 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 110 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top: Surface

BurstMax anticipated surface
pressure: -58 psi
Internal gradient: 0.456 psi/ft
Calculated BHP 1,082 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)Tension is based on buoyed weight.
Neutral point: 2,192 ft

Non-directional string.

Re subsequent strings:Next setting depth: 7,500 ft
Next mud weight: 8.330 ppg
Next setting BHP: 3,245 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 7,500 ft
Injection pressure 7,500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	2500	9.625	36.00	K-55	ST&C	2500	2500	8.765	29315
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1082	2020	1.87	1082	3520	3.25	79	423	5.36 J

Prepared RJK
by: Utah Dept. of Natural ResourcesDate: January 6,2000
Salt Lake City, Utah**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 2500 ft, a mud weight of 8.33 ppg The casing is considered to be evacuated for collapse purposes.
In addition, burst strength is biaxially adjusted for tension.*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	1-00 Coastal Hall 31-130	
Operator:	Coastal	Project ID:
String type:	Production	43-047-33427
Location:	Uintah County	

Design parameters:

Collapse

Mud weight: 11.000 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 236 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.571 psi/ft
Calculated BHP 6,571 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 9,582 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	11500	5.5	17.00	S-95	LT&C	11500	11500	4.767	94667
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	6571	8580	1.31	6571	9190	1.40	163	392	2.41 J

Prepared by: RJK
Utah Dept. of Natural Resources

Date: January 6,2000
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE


Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.
Collapse is based on a vertical depth of 11500 ft, a mud weight of 11 ppg The casing is considered to be evacuated for collapse purposes.
In addition, burst strength is biaxially adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

1-00 Coastal Hall 31-130

Casing Schematic

Cement TOPS w/
— % hole washout



ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: COASTAL OIL & GAS CORP.

WELL NAME & NUMBER: HALL 31-130

API NUMBER: 43-047-33427

LEASE: FEE **FIELD/UNIT:** OURAY

LOCATION: 1/4, 1/4 NW/NE SEC: 31 TWP: 8S RNG: 22E
2150' F E L 705' F N L

LEGAL WELL SITING: Statewide 400 foot window in center of 40
acre tract and no closer than 920 feet from
another well; or Board Spaced area requiring
Setback and From another well.

GPS COORD (UTM): 12629501E 4438253N

SURFACE OWNER: DAVID AND LYNN HALL

PARTICIPANTS:

TIM CHERVICK, CAROLL WILSON, KENNETH WILSON, (C.O.G.C.); ROBERT
KAY, (U.E.L.S.); LYNN HALL, DAVID HALL, (LAND OWNERS); THREE DIRT
CONTRACTORS; DAVID HACKFORD, (D.O.G.M.)

REGIONAL/LOCAL SETTING & TOPOGRAPHY:

SITE IS IN A RELATIVELY FLAT AREA 1.8 MILES NORTH OF WHITE RIVER.
SHIP ROCK IS 0.5 MILES EAST. THERE IS A SHARP CLAY HOGBACK
RIDGE 0.3 MILES NORTHWEST OF SITE.

SURFACE USE PLAN:

CURRENT SURFACE USE: WILDLIFE AND LIVESTOCK GRAZING.
HUNTING.

PROPOSED SURFACE DISTURBANCE: LOCATION WOULD BE 325' BY 245'
AND ACCESS ROAD WOULD BE 0.2 MILES.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: SEE
ATTACHED MAP FROM GIS DATABASE.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: _____
ALL PRODUCTION FACILITIES WILL BE ON A CO-MINGLE TANK
BATTERY LOCATED 0.5 MILES SOUTHWEST OF SITE. THE PIPELINE
TO THIS BATTERY WILL FOLLOW ACCESS ROAD.

SOURCE OF CONSTRUCTION MATERIAL: ALL CONSTRUCTION MATERIAL
WILL BE BORROWED FROM SITE DURING CONSTRUCTION OF LOCATION.

ANCILLARY FACILITIES: NONE WILL BE REQUIRED.

WASTE MANAGEMENT PLAN:

DRILLED CUTTINGS WILL BE SETTLED INTO RESERVE PIT. LIQUIDS
FROM PIT WILL BE ALLOWED TO EVAPORATE. FORMATION WATER WILL
BE CONFINED TO STORAGE TANKS. SEWAGE FACILITIES, STORAGE
AND DISPOSAL WILL BE HANDLED BY COMMERCIAL CONTRACTOR. TRASH
WILL BE CONTAINED IN TRASH BASKETS AND HAULED TO AN APPROVED
LAND FILL.

ENVIRONMENTAL PARAMETERS:

AFFECTED FLOODPLAINS AND/OR WETLANDS: NONE

FLORA/FAUNA: NATIVE GRASSES, GREASEWOOD, PRICKLY PEAR, CHEAT
GRASS, RUSSIAN THISTLE: RODENTS, COYOTES, SONGBIRDS,
RAPTORS, PRONGHORN.

SOIL TYPE AND CHARACTERISTICS: LIGHT RED SANDY CLAY.

EROSION/SEDIMENTATION/STABILITY: VERY LITTLE NATURAL
EROSION. SEDIMENTATION AND STABILITY ARE NOT A PROBLEM AND
LOCATION CONSTRUCTION SHOULDN'T CAUSE ANY INCREASE IN
STABILITY OR EROSION PROBLEMS.

PALEONTOLOGICAL POTENTIAL: NONE SITED.

RESERVE PIT:

CHARACTERISTICS: 100' BY 100' AND 10' DEEP.

LINER REQUIREMENTS (Site Ranking Form attached): _____

A LINER WILL NOT BE REQUIRED FOR RESERVE PIT.

SURFACE RESTORATION/RECLAMATION PLAN:

AS PER LANDOWNER AGREEMENT OR AS DIRECTED BY DIVISION.

SURFACE AGREEMENT: A SURFACE AGREEMENT HAS NOT BEEN SIGNED AT THIS TIME.

CULTURAL RESOURCES/ARCHAEOLOGY: SITE WAS INSPECTED BY MONTGOMERY ARCHAEOLOGICAL CONSULTANTS. A REPORT OF THIS INVESTIGATION WILL BE PLACED ON FILE.

OTHER OBSERVATIONS/COMMENTS:

THE PRE-DRILL INVESTIGATION TOOK PLACE ON 12/20/99, A COLD, WINDY DAY. GROUND WAS 25% COVERED WITH SNOW.

ATTACHMENTS:

PHOTOS OF SITE, PIT RANKING, STATEMENT OF BASIS.

DAVID W. HACKFORD
DOGM REPRESENTATIVE

12/20/99-10:45 AM
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and On-site Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>10</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	15	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>0</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	15	
TDS >10000 or Oil Base	20	
Mud Fluid containing high levels of hazardous constituents		<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility		
Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>
Final Score		<u>15</u>


Hall 31-130











STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such purposes

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone Number.

P.O. Box 1148, Vernal UT 84078

(435)-781-7023

4. Location of Well

Footages: 705' FNL & 2150' FEL

QQ, Sec., T., R., M.: NWNE Sec. 31, T8S, R22E

5. Lease Designation and Serial Number

FEE

6. Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

N/A

8. Well Name and Number:

Ouray #31-130

9. API Well Number:

43-047-33427

10. Field and Pool, or Wildcat

Ouray

County: Uintah County

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other | Name Change |

Approximate date work will start 12/9/99

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon* | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other | |

Date of work completion

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Coastal Oil & Gas Corporation requests authorization to change the name of the subject well from the Ouray #31-130 to Hall #31-130.


RECEIVED

DEC 10 1999

DIVISION OF OIL, GAS AND MINING

13

Name & Signature



Title

Sheila Upchego

Environmental Jr. Analyst


Date 12/9/99

(This space for State use only)

**BEFORE THE DIVISION OF OIL, GAS AND MINING
DEPARTMENT OF NATURAL RESOURCES
STATE OF UTAH**

IN THE MATTER OF THE
APPLICATION OF COASTAL OIL
AND GAS CORPORATION FOR A
PERMIT TO DRILL OR RE-ENTER
THE HALL #30-143, HALL #30-144,
HALL #31-99, HALL #31-130, HALL
#31-131, HALL #31-133, HALL #31-
134, HALL #6-136 and HALL #6-137
WELLS IN THE OURAY FIELD IN
UINTAH COUNTY, UTAH,
PURSUANT TO R649-3-34 OF THE
GENERAL RULES AND
REGULATIONS OF THE BOARD OF
OIL, GAS AND MINING
PERTAINING TO SURFACE USE
AND ACCESS AGREEMENTS

**AFFIDAVIT
OF
CARROLL A. WILSON**



STATE OF UTAH)
 : ss.
COUNTY OF UTAH)

CARROLL A. WILSON, being duly sworn, deposes and says that:

1. He is a citizen of the United States and a resident of Uintah County, Utah; and he is over the age of twenty-one years.
2. He is a Registered Land Professional, #22233, and a member in good standing with the American Association of Professional Landmen since January 1, 1975.
3. He is employed with Coastal Oil & Gas Corporation ("Coastal") as a Senior Landman for oil and gas operations in the Uinta Basin.

4. Coastal is a Delaware corporation in good standing, having its principal place of business in Houston, Texas. Coastal is authorized to do, and is doing, business in the State of Utah.

5. As a Senior Landman for Coastal, he is tasked with the acquisition of oil and gas leases, easements, and rights-of-way; and negotiations for settlement of entry fees and surface damages for access roads, pipelines, or wells drilled and operated by Coastal.

6. He is knowledgeable concerning Coastal's leasehold, access, and operational rights with respect to the following described privately owned lands in the Ouray Field of Uintah County, Utah, to wit:

Township 8 South, Range 22 East, S.L.M.

Section 30: Lot 4, SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1, Lot 2, E $\frac{1}{2}$ NW $\frac{1}{4}$, W $\frac{1}{2}$ NE $\frac{1}{4}$,

Township 9 South, Range 22 East, S.L.M.

Section 6: Lot 2, SW $\frac{1}{4}$ NE $\frac{1}{4}$,


(containing 441.51 acres, more or less)

7. He is familiar with Rule R659-3-34 of the General Rules and Regulations of the Utah Board of Oil, Gas and Mining ("**Board**") pertaining to surface use and access and to well site restoration.


8. He represents that the surface and mineral estates are integrated as one estate owned by the same party or parties who are also the lessors of record of the existing oil and gas leases, or their successors in title.


9. He represents that surface use and access rights affecting these lands are governed by the terms of those certain Oil and Gas Leases dated July 22, 1977, between the owners and Continental Oil Company (also known as "Conoco Inc."), Coastal's immediate predecessor in title.

DATED this 28th day of January, 2000.


Carroll A. Wilson

SUBSCRIBED TO AND SWORN before me this 28 day of January, 2000.




Notary Public

My Commission Expires:



January 31, 2000

State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 12010
Salt Lake City, UT 84180

Attention: Ms. Lisha Cordova

RECEIVED
FEB 02 2000
DIVISION OF
OIL, GAS AND MINING

Re: Ouray Field Development
Surface Use Agreements
Fourteen Development Wells
Uintah County, Utah

Dear Ms. Cordova:

Coastal Oil & Gas Corporation, either through its own regulatory personnel or through Buys & Associates, Inc., has filed Application's For Permit To Drill fourteen development wells in the Ouray Field on privately owned lands located in Sections 35 and 36, Township 8 South, Range 21 East; Sections 30 and 31, Township 8 South, Range 22 East; Section 1, Township 9 South, Range 21 East; and Section 6, Township 9 South, Range 22 East. You have asked for Coastal to furnish surface use agreements in compliance with R649-3-24.3 of the General Rules and Regulations of the Board of Oil, Gas and Mining in order for the Applications to be processed and approved.

After consultation with counsel, and Mr. John Baza of the Division, the following documents and materials are enclosed:

- 1) A copy of a letter from Mr. Phillip Lear of the firm of Snell & Wilmer, L.L.P., documenting his discussion with Mr. Baza and addressing the need for surface use agreements under R649-3-24.3 the in cases where the surface and mineral estates are combined and covered by a valid oil and gas lease;
- 2) Original Affidavits (3) given by myself to document ownership of the lands involved with the fourteen Applications; and

Coastal Oil & Gas Corporation


A SUBSIDIARY OF THE COASTAL CORPORATION
1368 S 1200 E • P.O. BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

ESMTS-00.023

- 3) Copies of the surface agreements which have been acquired to date under the terms of the various oil and gas leases applicable to the lands involved with the fourteen Applications which agreements are being provided as an act of good faith, inasmuch as Mr. Lear's letter indicates that, according to his conversations with Mr. Baza, only the Affidavit's are required under the regulations).

The final pre site inspections were conducted on January 20, 2000; and, if you now find everything in order, please complete the processing to approval of these fourteen Applications at your earliest convenience.

Very Truly Yours,

A handwritten signature in black ink, appearing to read 'Carroll A. Wilson', with a long horizontal line extending to the right.

Carroll A. Wilson
Sr. Landman

CC (letter only):

Cheryl Cameron - Regulatory Affairs

Martin Buys
Buys & Associates, Inc.

Snell & WilmerL.L.P.
LAW OFFICES111 East Broadway, Suite 900
Salt Lake City, Utah 84111
(801) 237-1900
Fax: (801) 237-1950

SALT LAKE CITY, UTAH

PHOENIX, ARIZONA

TUCSON, ARIZONA

IRVINE, CALIFORNIA

January 28, 2000

Carroll A. Wilson
Senior Landman
Coastal Oil & Gas Corporation
1176 East 1500 South
Vernal, UT 84078VIA FACSIMILE TRANSMISSION
(435) 789-4436**RECEIVED**

FEB 02 2000

DIVISION OF
OIL, GAS AND MININGRe: Surface Access and Use Agreements
Utah Admin. Code R649-3-34 (1999)

Dear Mr. Wilson:

You have inquired whether or not surface use agreements are necessary when conducting operations on an oil and gas lease on fee (private) lands. You advised me that the Utah Division of Oil, Gas and Mining ("Division") is holding your Application for Permit to Drill in abeyance pending you submitting a surface use agreement between Coastal Oil & Gas Corporation and the landowner. This letter contains our answer to your inquiry.

The oil and gas lease is, in part, a contract between the landowner and the lessee. When the surface and mineral ownership are the same, the lease embodies the entire agreement between the parties for both surface and subsurface use. No separate surface use agreement is necessary. (Citations omitted).

However, the General Rules and Regulations of the Board of Oil, Gas and Mining do require a surface use agreement covering well-site restoration of privately owned lands. See Utah Admin. Code R649-3-34.3 (1999). The requirement is that the well-site be restored according to the requirements of the surface owner; or when there is no surface use agreement with the surface owner, then according to the minimum standards established by the Division. See *id.* R649-3-24.3. The regulation applies when a new well is drilled, a plugged well is re-entered, or a new operator assumes operatorship of existing wells. See *id.* R649-3-34.6. This regulation contemplates both the leasehold involving consolidated mineral and surface estates or split estates, when the surface and minerals are owned by different parties. In the former situation, the lease constitutes the surface use agreement. In the latter, the oil and gas operator has no contractual relationship with the surface owner. To fully comply with the regulation, the operator submits an affidavit stating either that he has a surface use agreement or that no separate surface agreement is necessary because the oil and gas lease covers all rights of the parties. See R649-3-34.7. The affidavit should be submitted to the Division as part of the APD packet. *Id.*

Snell & Wilmer

LLP

Carroll A. Wilson

January 28, 2000


Page 2

This procedure has been confirmed by Mr. John R. Baza, Associate Director—Oil and Gas in recent discussions.

You raised the immediate question in the context of drilling a salt water disposal well on a private lease granted by a lessor who owns both the surface and mineral estates. The fact that the well is ultimately to be a salt water disposal well has no bearing on the interpretation of the regulation.

Should you have any further questions, please contact me.

Very truly yours,



Phillip Wm. Lear

cc: G. Len Miles
Donald H. Spicer
Carl F. Baker, Esq.

DAMAGE RELEASE

STATE OF Utah §

Gloucester COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **Norman Charles Larsen and Wanda Hall Larsen**, whose address is 59 East Lagoon, Roosevelt, UT 84066 for and in consideration of the payment of the sum of two hundred seventy four and 99/100 dollars (\$ 274.99), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$



**Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$**

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

AND, for the same consideration, the undersigned, **Norman Charles Larsen and Wanda Hall Larsen**, do hereby agree that every claim that they have, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 11 day of January,
2000.

Norman Charles Larsen **Wanda Hall Larsen**
59 East Lagoon (44-8) Roosevelt Utah 84066

SS # Norman Wanda
529-64-9807 528-76-2078

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW ¹ / ₄ SW ¹ / ₄)	Section 30, T8S, R22E
Hall #30-144	SE ¹ / ₄ SW ¹ / ₄	Section 30, T8S, R22E
Hall #31-99	NE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Hall #31-130	NW ¹ / ₄ NE ¹ / ₄	Section 31, T8S, R22E
Hall #31-131	SW ¹ / ₄ NE ¹ / ₄	Section 31, T8S, R22E
Hall #31-133	SE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW ¹ / ₄ NW ¹ / ₄)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW ¹ / ₄ NE ¹ / ₄)	Section 6, T9S, R22E
Hall #6-137	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E
CTB #E30S	SE ¹ / ₄ SW ¹ / ₄	Section 30, T8S, R22E
CTB #E31N	SE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF UTAH §

KNOW ALL MEN BY THESE PRESENTS:

UINTAH COUNTY §

THAT the undersigned **Acel M. Hall**, whose address is 402 South 1465 East, Fruit Heights, UT 84037, for and in consideration of the payment of the sum of nine hundred sixteen and 67/100 dollars (\$ 916.67), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$


Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

AND, for the same consideration, the undersigned, **Acel M. Hall**, does hereby agree that every claim that the he has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 13 day of Jan,
2000.


Acel M. Hall

SS # 528-22-0508

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$) Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$) Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$) Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF UTAH §

KNOW ALL MEN BY THESE PRESENTS:

WINTAH COUNTY §

THAT the undersigned **Acel M. Hall**, whose address is 402 South 1465 East, Fruit Heights, UT 84037, for and in consideration of the payment of the sum of nine hundred sixteen and 67/100 dollars (\$ 916.67), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$


Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

AND, for the same consideration, the undersigned, **Acel M. Hall**, does hereby agree that every claim that the he has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 13 day of Jan,
2000.


Acel M. Hall

SS # 528-22-0508

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

**Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$**

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$)	Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$)	Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF UTAH §
UTAH COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **William M. Hall as General Partner of the David B. Hall Family Partnership**, whose address is 2255 North University Parkway #15, Provo, UT 84604, for and in consideration of the payment of the sum of nine hundred sixteen and 67/100 dollars (\$ 916.67), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and do by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

**Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄**

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

AND, for the same consideration, the undersigned, **William M. Hall, General Partner**, does hereby agree that every claim that the Partnership has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 13 day of JANUARY,
2000.

David B. Hall Family Partnership

By: William M. Hall Gen'l Partner
William M. Hall, Gen'l Partner

Partnership Tax ID (or SS) # 84-1368142

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$) , SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$) Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$) Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$) Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF CA §

Riverside COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **Juanita Bergreen**, whose address is 1352 Birdsong Lane, Corona, CA 91719, for and in consideration of the payment of the sum of three hundred five and 56/100 dollars (\$ 305.56), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

**Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$**

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

AND, for the same consideration, the undersigned, **Juanita Bergreen**, does hereby agree that every claim that she has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 8 day of January,
2000.

Shirley Beeknap Juanita Bergreen
Juanita Bergreen

SS # 528-68-0894

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW ¹ / ₄ SW ¹ / ₄)	Section 30, T8S, R22E
Hall #30-144	SE ¹ / ₄ SW ¹ / ₄	Section 30, T8S, R22E
Hall #31-99	NE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Hall #31-130	NW ¹ / ₄ NE ¹ / ₄	Section 31, T8S, R22E
Hall #31-131	SW ¹ / ₄ NE ¹ / ₄	Section 31, T8S, R22E
Hall #31-133	SE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW ¹ / ₄ NW ¹ / ₄)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW ¹ / ₄ NE ¹ / ₄)	Section 6, T9S, R22E
Hall #6-137	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E
CTB #E30S	SE ¹ / ₄ SW ¹ / ₄	Section 30, T8S, R22E
CTB #E31N	SE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF Utah §
Uintah COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **Dee Ashby Hall and Alice Thurston Hall**, whose address is C/O 2800 West 1500 North, Vernal, UT 84078 for and in consideration of the payment of the sum of one hundred eighty three and 33/100 dollars (\$ 183.33), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

AND, for the same consideration, the undersigned, **Dee Ashby Hall and Alice Thurston Hall**, do hereby agree that every claim that they have, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 7 day of Jan,
2000.

Dee Ashby Hall
Dee Ashby Hall

Alice T. Hall
Alice Thurston Hall

SS # 528-44-7696

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$) , SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$)	Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$)	Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF Utah §
Morgan COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **Roland H. Sinfield**, whose address is PO Box 513, Morgan, UT 84050 for and in consideration of the payment of the sum of three hundred five and 56/100 dollars (\$ 305.56), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄


Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

AND, for the same consideration, the undersigned, **Roland H. Sinfield**, does hereby agree that every claim that the (s)he has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 10th day of January
2000.



Roland H. Sinfield

SS # 529-74-1551

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW ¹ / ₄ SW ¹ / ₄)	Section 30, T8S, R22E
Hall #30-144	SE ¹ / ₄ SW ¹ / ₄	Section 30, T8S, R22E
Hall #31-99	NE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Hall #31-130	NW ¹ / ₄ NE ¹ / ₄	Section 31, T8S, R22E
Hall #31-131	SW ¹ / ₄ NE ¹ / ₄	Section 31, T8S, R22E
Hall #31-133	SE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW ¹ / ₄ NW ¹ / ₄)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW ¹ / ₄ NE ¹ / ₄)	Section 6, T9S, R22E
Hall #6-137	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E
CTB #E30S	SE ¹ / ₄ SW ¹ / ₄	Section 30, T8S, R22E
CTB #E31N	SE ¹ / ₄ NW ¹ / ₄	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄	Section 6, T9S, R22E

STATE OF Utah \$
Uintah COUNTY \$

THAT the undersigned **Lynn S. Hall and Eula M. Hall Individually and as Trustees of the Lynn S. and Eula M. Hall Trust #3**, whose address is 2256 North 2500 west, Vernal, UT 84078, for and in consideration of the payment of the sum of nine hundred sixteen and 67/100 dollars (\$ 916.67), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and do by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$) , SW $\frac{1}{4}$ NE $\frac{1}{4}$

IN WITNESS WHEREOF, this release is executed this 6 day of Jan, 2000.

Enla-m, Hall

**Eula M. Hall, Individually and as Trustee
of the Lynn S. And Eula Hall Trust #3**

Lynn S. Hall

**Lynn S. Hall, Individually and as Trustee
of the Lynn S. And Eula Hall Trust #3**

Trust Tax ID (or SS) # 528-80-0445 ^{LSH} 529-097657 ^{emH.}

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$)	Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$)	Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF Utah §
Uintah COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **Jay M. Hall, Bruce B. Hall, Glade G. Hall, and Edwin C. Hall, Trustees of the Thomas Edwin Hall Testamentary Trust**, whose address is c/o Glade Hall, 965 Pinnocchio Drive, Salt Lake City, UT 84116, for and in consideration of the payment of the sum of five thousand five hundred and no/100 dollars (\$ 5,500.00), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, have released, discharged and acquitted and do by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

AND, for the same consideration, the undersigned, **Jay M. Hall, Bruce B. Hall, Glade G. Hall, and Edwin C. Hall Trustees**, do hereby agree that every claim that the Trust has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 7 day of January
2000.

Jay M Hall
Jay M. Hall, Trustee of the Thomas
Edwin Hall Testamentary Trust

Glade G Hall
Glade G. Hall, Trustee of the Thomas
Edwin Hall Testamentary Trust

Bruce B Hall
Bruce B. Hall, Trustee of the Thomas
Edwin Hall Testamentary Trust

Edwin C Hall
Edwin C. Hall, Trustee of the Thomas
Edwin Hall Testamentary Trust

Tax ID # 87-6180640

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$) Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$) Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$) Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF Utah §
Uintah COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **Vera Hall Murray and George Orland Murray**, whose address is 2800 West 1500 North, Vernal, UT 84078 for and in consideration of the payment of the sum of ninety one and 66/100 dollars (\$ 91.66), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

**Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄**

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

AND, for the same consideration, the undersigned, **Vera Hall Murray and George Orland Murray**, do hereby agree that every claim that they have, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 10 day of Jan,
2000.

Vera Hall Murray George Orland Murray
Vera Hall Murray George Orland Murray

SS # 528 - 62 - 3819

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$)	Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$)	Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF UTAH §
SALT LAKE COUNTY §

KNOW ALL MEN BY THESE PRESENTS:

THAT the undersigned **Grace Kimball**, whose address is 3232 South 1700 East, Salt Lake City, UT 84106, for and in consideration of the payment of the sum of nine hundred sixteen and 67/100 dollars (\$ 916.67), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$), SW $\frac{1}{4}$ NE $\frac{1}{4}$

AND, for the same consideration, the undersigned, **Grace Kimball**, does hereby agree that every claim that she has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 21ST day of JANUARY,
2000.

THE FOLLOWING ARE SIGNATURES OF LEGAL HEIRS OF GRACE KIMBALL
WHO IS DECEASED.

DHK

Grace Kimball

Don H. Kimball SS# 529-58-4678
Maysie K. Kastler Swenson SS# 528-52-9380
Rosemary Kimball Dadd SS# 528-46-1025

SS # _____

(OVER)

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

<u>Well Name</u>	<u>Location</u>
Hall #30-143	Lot 4 (SW ¹ / ₄ SW ¹ / ₄) Section 30, T8S, R22E
Hall #30-144	SE ¹ / ₄ SW ¹ / ₄ Section 30, T8S, R22E
Hall #31-99	NE ¹ / ₄ NW ¹ / ₄ Section 31, T8S, R22E
Hall #31-130	NW ¹ / ₄ NE ¹ / ₄ Section 31, T8S, R22E
Hall #31-131	SW ¹ / ₄ NE ¹ / ₄ Section 31, T8S, R22E
Hall #31-133	SE ¹ / ₄ NW ¹ / ₄ Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW ¹ / ₄ NW ¹ / ₄) Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW ¹ / ₄ NE ¹ / ₄) Section 6, T9S, R22E
Hall #6-137	SW ¹ / ₄ NE ¹ / ₄ Section 6, T9S, R22E
CTB #E30S	SE ¹ / ₄ SW ¹ / ₄ Section 30, T8S, R22E
CTB #E31N	SE ¹ / ₄ NW ¹ / ₄ Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄ Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW ¹ / ₄ NE ¹ / ₄ Section 6, T9S, R22E

DAMAGE RELEASE

STATE OF Utah §

KNOW ALL MEN BY THESE PRESENTS:

Uintah COUNTY §

THAT the undersigned **Merlin Sinfield**, whose address is 2550 West 1500 North, Vernal, UT 84078, for and in consideration of the payment of the sum of three hundred five and 56/100 dollars (\$ 305.56), paid by Coastal Oil & Gas Corporation (Coastal) the full receipt and sufficiency of which is hereby acknowledged, has released, discharged and acquitted and does by these presents hereby release, discharge and acquit Coastal, its parent and affiliates, its and their officers, directors, employees and agents, its successors and assigns of any and all liability to the undersigned, their heirs and assigns for any and all damages to land surface and grass and/or crops thereon, resulting from operations conducted by or on behalf of Coastal on the following described tract of land:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW¹/₄SW¹/₄), SE¹/₄SW¹/₄, SW¹/₄SE¹/₄

Section 31: Lot 1 (NW¹/₄NW¹/₄), Lot 2 (SW¹/₄NW¹/₄), E¹/₂NW¹/₄,
W¹/₂NE¹/₄

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE¹/₄NE¹/₄), Lot 2 (NW¹/₄NE¹/₄), SW¹/₄NE¹/₄

AND, for the same consideration, the undersigned, **Merlin Sinfield**, does hereby agree that every claim that the (s)he has, or may have, as a result of any operations conducted by or on behalf of Coastal, including construction of necessary access roads, remote production facilities or pipelines and including operations for drilling, completing, equipping and producing nine wells, two central tank batteries and two pipelines **described on Exhibit "A", attached hereto and made a part hereof**, is in all things fully satisfied, released and discharged. Further, the undersigned does hereby agree to exonerate, indemnify, protect, defend, hold harmless and save Coastal, its officers, employees, agents and shareholders from and against any claims, damages, causes of action, suits, costs and attorney fees, including third party claims for injury to real or personal property damage from or in connection with operation for construction, drilling, completing, equipping and producing the aforesaid wells and facilities.

IN WITNESS WHEREOF, this release is executed this 19 day of JANUARY,
2000.



Merlin Sinfield

SS # 529-74-4989

EXHIBIT "A"

Attached to and Made a Part of a Damage Release Covering the Following Described Lands:

Township 8 South, Range 22 East, SLB&M

Section 30: Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$), SE $\frac{1}{4}$ SW $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$

Section 31: Lot 1 (NW $\frac{1}{4}$ NW $\frac{1}{4}$), Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$), E $\frac{1}{2}$ NW $\frac{1}{4}$,
W $\frac{1}{2}$ NE $\frac{1}{4}$

Township 9 South, Range 22 East, SLB&M

Section 6: Lot 1 (NE $\frac{1}{4}$ NE $\frac{1}{4}$), Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$) , SW $\frac{1}{4}$ NE $\frac{1}{4}$

<u>Well Name</u>	<u>Location</u>	
Hall #30-143	Lot 4 (SW $\frac{1}{4}$ SW $\frac{1}{4}$)	Section 30, T8S, R22E
Hall #30-144	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
Hall #31-99	NE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-130	NW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-131	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-133	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Hall #31-134	Lot 2 (SW $\frac{1}{4}$ NW $\frac{1}{4}$)	Section 31, T8S, R22E
Hall #6-136	Lot 2 (NW $\frac{1}{4}$ NE $\frac{1}{4}$)	Section 6, T9S, R22E
Hall #6-137	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
CTB #E30S	SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section 30, T8S, R22E
CTB #E31N	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Section 31, T8S, R22E
Tribal #6-139 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E
Tribal #6-100 (60' wide ROW for pipeline connection only)	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Section 6, T9S, R22E



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Kathleen Clarke
Executive Director

Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

February 3, 2000

Coastal Oil & Gas Corporation
P.O. Box 1148
Vernal, Utah 84078

Re: Hall 31-130 Well, 705' FNL, 2150' FEL, NW NE, Sec. 31, T. 8 S, R. 22 E Uintah
County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33427.

Sincerely,

A handwritten signature in black ink, appearing to read 'John R. Baza'.
John R. Baza
Associate Director

jb

Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Coastal Oil & Gas

Well Name & Number: Hall 31-130

API Number: 43-047-33427

Lease: FEE

Location: NW NE **Sec.** 31 **T.** 8 S. **R.** 22 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division of the following actions during drilling of this well:

24 hours prior to cementing or testing casing

24 hours prior to testing blowout prevention equipment

24 hours prior to spudding the well

within 24 hours of any emergency changes made to the approved drilling program
prior to commencing operations to plug and abandon the well

Division contacts (please leave a voice mail message if person is not available to take the call):

Dan Jarvis at (801)538-5338

Robert Krueger at (801)538-5274 (plugging)

Carol Daniels at (801)538-5284 (spud)

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

FORM 9

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such purposes

1. Type of Well: OIL ☐ GAS ☒

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone Number.

P.O. Box 1148, Vernal UT 8

4. Location of Well

Footages: 705' FNL & 2150' FEL

QQ, Sec., T., R., M.: NWNE Sec. 31, T8S, R22E

5. Lease Designation and Serial Number

FEE

6. Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

CA #NRM 1887

8. Well Name and Number:

Hall #31-130

9. API Well Number:

43-047-33427

10. Field and Pool, or Wildcat

Ouray

(435)-781-7023

County: Uintah

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>Surface/TD Change</u> | |

Approximate date work will start Immediate

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon* | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Date of work completion _____


Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Coastal Oil & Gas Corporation requests authorization to change the TD from 11500' to 7300' to the Wasatch formation. The surface casing depth will change from 2500' to 900'.

Please refer to the attached Drilling Program. - Blm noted - (Wayne Bankert) on 3/14/00
sn



13. Name & Signature Sheila Upchego Title Environmental Jr. Analyst

Date 3/14/00

(This space for State use only)

APPROVED

The Utah Division of Oil, Gas and Mining
Robert J. Krueger, PE, Petroleum Engineer.

Date: 3-15-00

Well name:	1-00 Coastal Hall 31-130	
Operator:	Coastal	
String type:	Surface	Project ID: 43-047-33427
Location:	Uintah County	

Design parameters:

Collapse

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface pressure: -21 psi
Internal gradient: 0.456 psi/ft
Calculated BHP 389 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 787 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 7,500 ft
Next mud weight: 8.330 ppg
Next setting BHP: 3,245 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 7,500 ft
Injection pressure 7,500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	900	8.625	24.00	K-55	ST&C	900	900	7.972	7545
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	389	1370	3.52	389	2950	7.57	19	263	13.92 J

Prepared RJK
by: Utah Dept. of Natural Resources

Date: March 15,2000
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.
Collapse is based on a vertical depth of 900 ft, a mud weight of 8.33 ppg The casing is considered to be evacuated for collapse purposes.
In addition, burst strength is biaxially adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	1-00 Coastal Hall 31-130	
Operator:	Coastal	
String type:	Production	Project ID: 43-047-33427
Location:	Uintah County	

Design parameters:

Collapse

Mud weight: 11.000 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 177 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.571 psi/ft
Calculated BHP 4,171 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 6,100 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	7300	4.5	11.60	K-55	LT&C	7300	7300	3.875	31825
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4171	4960	1.19	4171	5350	1.28	71	180	2.54 J

Prepared RJK
by: Utah Dept. of Natural Resources

Date: March 15,2000
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE


Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 7300 ft, a mud weight of 11 ppg. The casing is considered to be evacuated for collapse purposes. In addition, burst strength is biaxially adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

3-00 Coastal Hall 31-130

Casing Schematic



COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

DRILLING PROGRAM

COMPANY NAME	Coastal Oil & Gas Corporation	DATE	3/14/00
WELL NAME	Hall #31-130	TD	7,300' MD/TVD
FIELD	Ourray	COUNTY	Uinlah
		STATE	Utah
		ELEVATION	4,740' KB
SURFACE LOCATION	750' FNL & 2,150' FEL Sec 31, T8S-R22E		
OBJECTIVE ZONE(S)	Green River, Wasatch		
ADDITIONAL INFO	BHL Straight Hole		


WELL NAME	Hall #31-130	DATE	3/14/00
		TD	7,300' MD/TVD

FIELD	Ouray	COUNTY Uintah	STATE Utah	ELEVATION 4,740'	KB
-------	-------	---------------	------------	------------------	----

SURFACE LOCATION 750' FNL & 2,150' FEL Sec 31, T8S-R22E BHL Straight Hole

OBJECTIVE ZONE(S) Green River, Wasatch

ADDITIONAL INFO



CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
SURFACE	8-5/8"	0-900'	24#	K-55	STC	2950	1730	263000
						5.84	4.11	3.67
PRODUCTION*	4-1/2"	0-TD	11.6#	K-55	LTC	5350	4960	180000
						2.08	1.31	1.34

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
- 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
- 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
- (Burst Assumptions: FG @ 8-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50,000 lbs overpull)
- *Utilize 5-1/2", 17#, N-80 if 4-1/2" is not available.

CEMENT PROGRAM


	FT. OF FILL	DESCRIPTION	SACKS	EXCESS*	WEIGHT	YIELD
SURFACE	900	Class G + 2% CaCl ₂ + 0.25 lb/sk Cello Flake	280	35%	15.80	1.17
PRODUCTION	5000	Premium Lite II + 3 lb/sk CSE + 0.5% Sodium Metasilicate + 10% Gel + 0.25 lb/sk Cello Flake + 3% Salt + 3 lb/sk Kol Seal	810	150%	11.00	3.44
	2300	50/50 POZ + 0.1% R-3 + 1% EC-1 + 0.2% Sodium Metasilicate + 2% Gel + 0.5% FL-25 + 3% Salt	750	75%	14.5	1.23

* or 15% over caliper log

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to surface with bow spring centralizers. Thread lock FE up to & including pin end of FC.
PRODUCTION	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

WELLHEAD EQUIPMENT



TREE	2-1/16" 5M
TUBING HEAD	11" 3M X 7-1/16" 5M
CASING SPOOL	
CASING SPOOL	
CASING HEAD	8-5/8" SOW X 11" 3M

BIT PROGRAM

INTERVAL	HOLE	BIT MFG & MODEL	GPM	SERIAL	NZLS	COMMENTS
Surface Hole	11"	Various				
Surf Csg - TD	7-7/8"	F-45H	Air/Mist	New	16-16-16	
			Aerated			
If 2nd bit is required	7-7/8"	G536 or equivalent PDC	350-300	Rental	0.5 sqin TFA	No air if circulation possible
		(3/4" cutters, 5 or 6 blades)				

7-7/8" F-45H: Run 50,000# WOB (app. 25 DC's) & turn rotary at +/- 70 RPM.
Run PDC bit if primary bit fails to reach TD.
7-7/8" G536 PDC: Run 10,000-20,000 # WOB & turn rotary at 50 - 80 RPM.
Nozzle down PDC to 0.5 sqin TFA.

GEOLOGICAL DATA

LOGGING:

Depth	Log Type
	No Open Hole Logs

MUD LOGGER:	4,000' - TD only if required by Geology
SAMPLES:	As per Geology
CORING:	NA
DST:	NA

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER LOSS	VISCOSITY	TREATMENT
0-Trona (0 - +/-2,000')	Air/Mist	NA	NA		2% KCl
Trona-TD (+/- 2,000' - TD)	Aerated Water	NA	NC	NA	2% KCl, Polymer, LCM if required

Circulate hole until clean @ TD. Spot viscosified pill at TD for casing. Minimize corrosion chemicals.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.
BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.
Run Totco surveys @ 2,000' & 4,000'. Maximum allowable hole angle is 5 degrees.

PROJECT ENGINEER:

Blaine Yeary

PROJECT MANAGER:

Ben Clark

DATE:

DATE:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW/NE Sec.31, T8S.R22E
705'FNL & 2150'FEL

5. Lease Serial No.

FEE

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA/Agreement, Name and/or No.
CA #NRM 1887

8. Well Name and No.

Hall #31-130

9. API Well No.

43-047-33427

10. Field and Pool, or Exploratory Area
Ouray

11. County or Parish, State

Uintah UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- | | | | |
|---|---|--|---|
| <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other <u>Spud</u> |
| <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon | |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

3/12/00 - MIRU Malcolms Rathole (Bucket Rig). Drilled 50' of 18" hole. Ran 50' of 14" conductor pipe. Cmt w/60 sks P-AG w/2% CaCl2, 1/4#/sk Flocele, 15.6 ppg, 1.18 yield. Hole stayed full.
3/14/00 - MIRU Bill Martin Drilling (Air Rig). Drilled 918' of 12 1/4" hole. Ran 20 jts of 8 5/8" 24# K-55 Csg. Cmt w/190 sks HCL w/2% CaCl2, 1/4#/sk Flocele, 12.7 ppg, 1/82 yield. Tail w/160 sks P-AG w/2% CaCl2, 1/4#/sk Flocele, 15.6 ppg, 1/19 yield. Drop plug. Displace w/ 55 Bbls H2O. Hole full.

Spud @ 2:30 p.m. on 3/12/2000

RECEIVED

MAR 17 2000

DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Katy Dow

Title

Environmental Jr. Analyst

Date

3/20/00

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW/NE Sec.31, T8S, R22E
705' FNL & 2150' FEL

5. Lease Serial No.

Fee

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA/Agreement, Name and/or No.
CA #NRM 1887

8. Well Name and No.

Hall #31-130

9. API Well No.

43-047-33427

10. Field and Pool, or Exploratory Area

Ouray

11. County or Parish, State

Uintah UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other Drilling

Summary

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Finished drilling from 918' to 7305'. Ran 170 jts 5 1/2" 17# N-80 Csg. Cmt w/458 sks Class "G" w/adds. 11.0 ppg. 3.79 yield. Tail w/590sks 50/50 Poz w/adds, 14.3 ppg. 1.27 yield. Drop plug. Displace w/169 Bbls 2/3 KCL. Plug down. Rig released @ 8:00 a.m. on 3/29/00.

RECEIVED

APR 03 2000

**DIVISION OF
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Katy Dow

Title

Environmental Jr. Analyst

Date 3/30/00

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

Fee

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA/Agreement, Name and/or No.
CA #NRM 1887

8. Well Name and No.

Hall #31-130

9. API Well No.

43-047-33427

10. Field and Pool, or Exploratory Area
Ouray

11. County or Parish, State

Utah UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW/NE Sec.31,T8S,R22E
705'FNL & 2150'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other Completion

Report

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Subject well placed on production on 4/19/00. Please refer to the attached Chronological Well History.

RECEIVED

MAY 01 2000

**DIVISION OF
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Katy Dow

Title

Environmental Jr. Analyst

Date 4/27/00

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

COASTAL OIL & GAS CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

HALL 31-130

OURAY FIELD
UINTAH COUNTY, UT
WI: 100% AFE: 90163
PBTD: PERFS:
CSG:
FORMATION: WASATCH
CWC(M\$):

RECEIVED

MAY 01 2000

DIVISION OF
OIL, GAS AND MINING

DRILL & COMPLETE

Drilling: , Spud Date: 03/17/00.

04/04/00 **EVALUATING LOGS.**
PROG: MIRU. PU 4 3/4" BIT & RIH TO PBTD @ 7248'. CIRC HOLE CLEAN. PU TO 5077'.
(DAY 1)

04/05/00 **PREP TO RUN CASED HOLE LOG.**
PROG: SI EVALUATING LOGS.

04/06/00 **W.O. LOG EVALUATION.**
PROG: POOH W/ 2 3/8" TBG. RUN COMPULOG'S PULSED NEUTRON DENSITY LOG
F/ 5200' TO PBTD @ 7231'. (DAY 2)

04/07/00 **PREP TO PERF.**
PROG: EVALUATING LOGS.

04/08/00 **PREP TO FRAC.**
PROG: PERF WASATCH 6438' TO 6448', 4 SPF, 40 HOLES & 6412' - 6418', 4 SPF, 24 HOLES,
& 6366' - 6378', 4 SPF, 48 HOLES. FL @ SURF, 0 PRESS. BRK DN PERFS W/ 1300# @ 4.5
BPM. ISIP: 800#. (DAY 3)

04/09/00 **PREP TO DO CBP'S.**
PROG: FRAC WASATCH PERFS 6366' - 6448'. BRK DN W/ 1108# @ 3 BPM. FRAC W/
110,000# 20/40 SD W/ 15%. PROP NET & YF125 LG FLUID/GEL. MTP: 2522#, ATP: 1586#,
MTR: 46.6 BPM, ATR: 38.2 BPM, ISIP: 1250#, FG: 0.54, TL: 991 BBLS. SET CBP @ 6230'. PERF
WASATCH 5898' - 5902', 4 SPF, 36 HOLES; 5886' - 5892', 4 SPF, 24 HOLES; AND 5878' - 5880',
4 SPF 8 HOLES. 0 PRESS. BRK DN W/ 3506# @ 3.2 BPM. FRAC W/ 57,880# 20/40 SD W/
15% PROP NET & YF125 LG FLUID/GEL. ISIP: 2028#. MTP: 3273#, ATP: 2413#, MTR: 36
BPM, ATR: 25.5 BPM, FG: 0.79. TL: 585 BBLS. SET CPB @ 5750'. PU & SIH W/ 4 3/4" BIT.
EOT @ 5600'. (DAY 4)

04/10/00 **FLWG BACK.**
PROG: RIH & DO CBP'S @ 5750' & 6230'. CO TO PBTD @ 7248'. CIRC HOLE CLEAN. PU
& LAND TBG @ 6442', SN @ 6408'. OPEN TO FBT @ 2:00 PM. FLOW BACK 17 HRS. CK
48/64". CP: 700# TO 90#, FTP: 250# TO 290#, 19 BWPH TO 3 BWPH, NO SAND, TLTR: 1586
BBLS, TLR: 743 BBLS, LLTR: 843 BBLS. (DAY 5)

04/11/00 SITP: 1850#, CP: 1700#. SI WO PIPELINE.

04/12/00 TBG 2000#, CSG 1800#. SI. WO PIPELINE CONNECTION.

04/13/00 SI. WO PIPELINE CONNECTION.

04/20/00 **PROG: PLACED ON SALES @ 11 AM, 4/19/00. SPOT PRODUCTION DATA: FLWG 1.7**
MMCFPD, FTP: 1660#, CP: 2000#, 15/64" CK, 2 BWPH.

04/21/00 **PROG: FLWD 2693 MCF, 0 BW, FTP: 550#, CP: 1095#, 30/64" CHK, 20 HRS, LP: 169#, LLTR:**
843#.

04/22/00 **PROG: FLWD 3046 MCF, 0 BW, FTP: 400#, CP: 914#, 32/64" CHK, 24 HRS, LP: 156#, LLTR:**
843 BBLS.

04/23/00 PROG: FLWD 2725 MCF, 0 BW, FTP: 350#, CP: 814#, 34/64" CHK, 24 HRS, LP: 152#, LLTR:
843 BBLS.

04/24/00 PROG: FLWD 2519 MCF, 0 BW, FTP: 220#, CP: 732#, 40/64" CHK, 24 HRS, LP: 150#, LLTR:
843 BBLS.

IP DATE: 4/21/00 - FLWG 3046 MCF, 0 BW, FTP: 400#, CP: 914#, 32/64" CHK, 24 HRS, LP:
156#.

FINAL REPORT.

RECEIVED
MAY 01 2000
DIVISION OF
OIL, GAS AND MINING

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR Coastal Oil & Gas Corp
ADDRESS 1368 W. 1200 E.
Jordan, Ut
84078

OPERATOR ACCT. NO. 11

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION				COUNTY	SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG			
A	99999	12738	43-047-33427	Hall-21-130	WINE	31	85	22E	Uintah	3/12/00	3/12/00
WELL 1 COMMENTS: 000523 entity added.											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

Katy H. Paul
Signature
Environmental Jr. Analyst
Title
5/23/00
Date
Phone No. 435 781-7022

STATE OF UTAH

DIVISION OF OIL, GAS AND MINING

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ Other _____
 b. TYPE OF COMPLETION: NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other _____

2. NAME OF OPERATOR

Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR

P.O. Box 1148, Vernal UT 84078

(435)-781-7023

4. LOCATION OF WELL (Report location clearly and in accordance with any State 2000 rements)

At surface

NWNE

At top prod. interval reported below

705' FNL & 2150' FEL

At total depth

RECEIVED

DIVISION OF
OIL, GAS AND MINING

14. API NO.

43-047-33427

DATE ISSUED

2-3-00

5. LEASE DESIGNATION AND SERIAL NO.

FEE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

CA #NRM 1887

8. FARM OR LEASE NAME

Hall

9. WELL NO.

#31-130

10. FIELD AND POOL, OR WILDCAT

Ouray

11. SEC., T., R., M., OR BLK.
AND SURVEY OR AREA

Sec. 31, T8S, R22E

12. COUNTY

Uintah

13. STATE

Utah

15. DATE SPUDED

3/12/00

16. DATE T.D. REACHED

3/29/00

17. DATE COMPL.

4/19/00

(Ready to prod.)
or
(Plug & Abd.)

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)

4720.5' GR

19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD

7305'

21. PLUG, BACK T.D., MD & TVD

7261'

22. IF MULTIPLE COMPL.,
HOW MANY23. INTERVALS
DRILLED BY

ROTARY TOOLS

X

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)

Wasatch 6438' - 6448', 6412' - 6418', 6366' - 6378', 5898' - 5902', 5886' - 5892', 5878' - 5880'

25. WAS DIRECTIONAL
SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

Nuetron Density, C/CLL, AL

3-31-2000

27. Was Well Cored YES ☐ NO ☒ (Submit analysis)
Drill System Test YES ☐ NO ☒ (See reverse side)

28. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
14" Conductor	Pipe	50'	18"	60 sx	
8 5/8"	24#	918'	12 1/4"	190 sx Lead, 160 sx Tail	
5 1/2"	17#	7305'	7 7/8"	458 dc Lead 590 sx 50/50 POZ	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"	7231'	

30. TUBING RECORD

31. PERFORATION RECORD (Interval, size and number)

Wasatch 6438' - 6448' 4 SPF 40 Holes, 6412' - 6418'

4 SPF 24 Holes, 6366' - 6378' 4 SPF 48 Holes,

5898' - 5902' 4 SPF 36 Holes, 5886' - 5892' 4 SPF 24 Holes,

5878' - 5880' 4 SPF 8 Holes

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
6366' - 6448'	110,000# 20/40 SD w/15% Prop Net & YF125 LG Fluid Gel.
5880' - 5902'	57,880# 20/40 SD w/15% Prop Net & YF 125 LG Fluid Gel

33. PRODUCTION

DATE FIRST PRODUCTION 4/20/00		PRODUCTION METHOD (Flowing, gas lift, pumping - size and type of pump) Flowing				WELL STATUS (Producing or shut-in) Producing	
DATE OF TEST 4/21/00	HOURS TESTED 24	CHOKE SIZE 32/64	PROD'N. FOR TEST PERIOD → 0	OIL - BBL. 0	GAS - MCF. 3046	WATER - BBL. 0	GAS - OIL RATIO
FLOW. TUBING PRESS. 400#	CASING PRESSURE 914#	CALCULATED 24-HOUR RATE → 0	OIL - BBL. 0	GAS - MCF. 0	WATER - BBL. 0	OIL GRAVITY - API (CORR.) 0	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold Used for fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

Chronological Well History

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Sheila Upchego
Environmental Jr. Analyst

DATE 4/27/00

See Spaces for Additional Data on Reverse Side

INSTRUCTIONS

This form should be completed in compliance with the Utah Oil and Gas Conservation General Rules. If not filed prior to this time, all logs, tests, and directional surveys as required by Utah Rules should be attached and submitted with this report.

- ITEM 18: Indicate which elevation is used as reference for depth measurements given in other spaces on this form and on any attachment.
- ITEMS 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22. and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.
- ITEM 29: "Sacks Cement": Attached supplemental records for this well should show the details for any multiple stage cementing and the location of the cementing tool.
- ITEM 33: Submit a separate completion report on this form for each interval to be separately produced (see instruction for items 22 and 24 above).

37. SUMMARY OF POROUS ZONES: Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries).			38. GEOLOGIC MARKERS				
Formation	Top	Bottom	Description, contents, etc.	Name	Meas. Depth	Top	True Vert. Depth
GREEN RIVER	2050'	5338'	<div>RECEIVED</div> <div>MAY 05 2000</div> <div>DIVISION OF OIL, GAS AND MINING</div>				
WASATCH	5338'						

COASTAL OIL & GAS CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

HALL 31-130

OURAY FIELD
UINTAH COUNTY, UT
PBSD: PERFS:
FORMATION: WASATCH

DRILL & COMPLETE

Drilling: , Spud Date: 03/17/00.

RECEIVED

MAY 05 2000

**DIVISION OF
OIL, GAS AND MINING**

04/04/00 **EVALUATING LOGS.**

PROG: MIRU. PU 4 3/4" BIT & RIH TO PBSD @ 7248'. CIRC HOLE CLEAN. PU TO 5077'.
(DAY 1)

04/05/00 **PREP TO RUN CASED HOLE LOG.**

PROG: SI EVALUATING LOGS.

04/06/00 **W.O. LOG EVALUATION.**

PROG: POOH W/ 2 3/8" TBG. RUN COMPULOG'S PULSED NEUTRON DENSITY LOG F/ 5200' TO PBSD @ 7231'.
(DAY 2)

04/07/00 **PREP TO PERF.**

PROG: EVALUATING LOGS.

04/08/00 **PREP TO FRAC.**

PROG: PERF WASATCH 6438' TO 6448', 4 SPF, 40 HOLES & 6412' - 6418', 4 SPF, 24 HOLES, & 6366' - 6378', 4 SPF, 48 HOLES. FL @ SURF, 0 PRESS. BRK DN PERFS W/ 1300# @ 4.5 BPM. ISIP: 800#.
(DAY 3)

04/09/00 **PREP TO DO CBP'S.**

PROG: FRAC WASATCH PERFS 6366' - 6448'. BRK DN W/ 1108# @ 3 BPM. FRAC W/ 110,000# 20/40 SD W/ 15%. PROP NET & YF125 LG FLUID/GEL. MTP: 2522#, ATP: 1586#, MTR: 46.6 BPM, ATR: 38.2 BPM, ISIP: 1250#, FG: 0.54, TL: 991 BBLS. SET CBP @ 6230'. PERF WASATCH 5898' - 5902', 4 SPF, 36 HOLES; 5886' - 5892', 4 SPF, 24 HOLES; AND 5878' - 5880', 4 SPF 8 HOLES. 0 PRESS. BRK DN W/ 3506# @ 3.2 BPM. FRAC W/ 57,880# 20/40 SD W/ 15% PROP NET & YF125 LG FLUID/GEL. ISIP: 2028#. MTP: 3273#, ATP: 2413#, MTR: 36 BPM, ATR: 25.5 BPM, FG: 0.79. TL: 585 BBLS. SET CPB @ 5750'. PU & SIH W/ 4 3/4" BIT. EOT @ 5600'.
(DAY 4)

04/10/00 **FLWG BACK.**

PROG: RIH & DO CBP'S @ 5750' & 6230'. CO TO PBSD @ 7248'. CIRC HOLE CLEAN. PU & LAND TBG @ 6442', SN @ 6408'. OPEN TO FBT @ 2:00 PM. FLOW BACK 17 HRS. CK 48/64". CP: 700# TO 90#, FTP: 250# TO 290#, 19 BWPH TO 3 BWPH, NO SAND, TLTR: 1586 BBLS, TLR: 743 BBLS, LLTR: 843 BBLS.
(DAY 5)

04/11/00 SITP: 1850#, CP: 1700#. SI WO PIPELINE.

04/12/00 TBG 2000#, CSG 1800#. SI. WO PIPELINE CONNECTION.

04/13/00 SI. WO PIPELINE CONNECTION.

04/20/00 PROG: PLACED ON SALES @ 11 AM, 4/19/00. SPOT PRODUCTION DATA: FLWG 1.7 MMCFPD, FTP: 1660#, CP: 2000#, 15/64" CK, 2 BWPH.

04/21/00 PROG: FLWD 2693 MCF, 0 BW, FTP: 550#, CP: 1095#, 30/64" CHK, 20 HRS, LP: 169#, LLTR: 843#.

04/22/00 PROG: FLWD 3046 MCF, 0 BW, FTP: 400#, CP: 914#, 32/64" CHK, 24 HRS, LP: 156#, LLTR: 843 BBLs.

04/23/00 PROG: FLWD 2725 MCF, 0 BW, FTP: 350#, CP: 814#, 34/64" CHK, 24 HRS, LP: 152#, LLTR: 843 BBLs.

04/24/00 PROG: FLWD 2519 MCF, 0 BW, FTP: 220#, CP: 732#, 40/64" CHK, 24 HRS, LP: 150#, LLTR: 843 BBLs.
IP DATE: 4/21/00 - FLWG 3046 MCF, 0 BW, FTP: 400#, CP: 914#, 32/64" CHK, 24 HRS, LP: 156#.

FINAL REPORT.

RECEIVED
MAY 05 2000
DIVISION OF
OIL, GAS AND MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

168 South 1200 East CITY Vernal STATE Utah ZIP 84078

PHONE NUMBER:

435-789-4433

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

COUNTY:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☐ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

TYPE OF ACTION

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: Name Change

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation

NAME (PLEASE PRINT)

John T. Elzner

TITLE Vice President

SIGNATURE

DATE

06-15-01

El Paso Production Oil & Gas Company

NAME (PLEASE PRINT)

John T. Elzner

TITLE

Vice President

SIGNATURE

DATE

06-15-01

(This space for State use only)

RECEIVED

JUN 19 2001

State of Delaware
Office of the Secretary of State

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



0610204 8100

010162788

Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

AUTHENTICATION: 1061007

DATE: 04-03-01

**CERTIFICATE OF AMENDMENT
OF
CERTIFICATE OF INCORPORATION**

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:

"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION



David L. Siddall
Vice President

Attest:


Margaret E. Roark, Assistant Secretary

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING

OPERATOR CHANGE WORKSHEET**ROUTING**

1. GLH		4-KAS
2. CDW ✓		5-LP
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X MergerThe operator of the well(s) listed below has changed, effective: **3-09-2001**

FROM: (Old Operator):
COASTAL OIL & GAS CORPORATION
Address: 9 GREENWAY PLAZA STE 2721
HOUSTON, TX 77046-0995
Phone: 1-(713)-418-4635
Account N0230

TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY
Address: 9 GREENWAY PLAZA STE 2721 RM 2975B
HOUSTON, TX 77046-0995
Phone: 1-(832)-676-4721
Account N1845

CA No.**Unit:****WELL(S)**

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
TODD USA ST 1-2B1 (CA NW-669)	43-047-30167	5530	02-02S-01W	FEE	OW	S
WINN P2-3B1E (CA 9C-145)	43-047-32321	11428	03-02S-01E	FEE	OW	P
HORROCKS 2-5B1E (CA 9C-129)	43-047-32409	11481	05-02S-01E	FEE	OW	P
STATE PICKUP 1-6B1E	43-047-30169	5970	06-02S-01E	FEE	OW	S
STATE 1-7B1E	43-047-30180	5695	07-02S-01E	FEE	OW	S
REYNOLDS 2-7B1E	43-047-31840	10878	07-02S-01E	FEE	OW	S
TIMOTHY 1-8B1E (CA 9C-141)	43-047-30215	1910	08-02S-01E	FEE	OW	P
PARIETTE DRAW 28-44	43-047-31408	4960	28-04S-01E	FEE	OW	P
LCK 30-1-H (CA 86C689)	43-047-31588	10202	30-06S-21E	FEE	OW	P
ANNE BELL 31-2-J	43-047-31698	10510	31-06S-21E	FEE	OW	P
STATE 35 WELL 52 (CA NRM 1604) (CA 9C-182)	43-047-32697	11856	35-08S-21E	FEE	GW	P
OURAY 35-94 (CA NRM 1604 (CA9C-182)	43-047-33053	12710	35-08S-21E	FEE	GW	P
OURAY 36-97	43-047-33397	12740	36-08S-21E	FEE	GW	P
HALL 30 WELL 58	43-047-32715	11849	30-08S-22E	FEE	GW	P
HALL 30-143	43-047-33425	12830	30-08S-22E	FEE	GW	P
HALL 30-144	43-047-33426	12724	30-08S-22E	FEE	GW	P
HALL ETAL 31-18 (CA NRM-1887) (CA 84688C)	43-047-30664	95	31-08S-22E	FEE	GW	P
HALL 31-99 (CA NRM-1887) (CA 84688C)	43-047-33390	12756	31-08S-22E	FEE	GW	P
HALL 31-130 (CA NRM-1887) (CA 84688C)	43-047-33427	12738	31-08S-22E	FEE	GW	P
HALL 31-134 (CA NRM-1887) (CA 84688C)	43-047-33428	12698	31-08S-22E	FEE	GW	P

OPERATOR CHANGES DOCUMENTATION

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
4. Is the new operator registered in the State of Utah: YES Business Number: 608186-0143

5. If NO, the operator was contacted contacted on: N/A
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: N/A
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: N/A
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: N/A
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 07/09/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 07/09/2001
3. Bond information entered in RBDMS on: 06/20/2001
4. Fee wells attached to bond in RBDMS on: 07/09/2001

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: N/A

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed has furnished a bond: 400JU0708
2. The **FORMER** operator has requested a release of liability from their bond on: COMPLETION OF OPERATOR CHANGE
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: COMPLETION OF OPERATOR CHANGE

FILMING:

1. All attachments to this form have been **MICROFILMED** on: _____

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: _____

COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".

JAN. 17. 2003 3:34PM

WESTPORT

NO. 173 P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5409

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Engineer Technician

Encl:



United States Department of the Interior **RECEIVED**

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

UNITED STATES GOVERNMENT

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.


We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chrono





United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

January 9, 2003

Westport Oil and Gas Company, L.P.
Attn: Gary D. Williamson
1670 Broadway, Suite 2800
Denver, Colorado 80202

Re: Successor of Operator
Communitization Agreement (CA)
NRM-1887
Uintah County, Utah

Gentlemen:

We received an indenture dated June 1, 2002, whereby El Paso Production Oil and Gas Company resigned as Operator and Westport Oil and Gas Company, L.P. was designated as Operator for CA NRM-1887, Uintah County, Utah.

This indenture was executed by all required parties. The instrument is hereby approved effective January 9, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under CA NRM-1887.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover CA operations.

Please advise all interested parties of the change in operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
Division Oil, Gas, & Mining
File - NRM-1887 (w/enclosure)
Agr. Sec. Chron
Fluid Chron

UT922:TATHOMPSON:tt:1/9/03

RECEIVED

JAN 10 2003


DIV. OF OIL, GAS & MINING

Results of query for MMS Account Number NRM1887

Production	API Number	Operator	Well Name	Well Status	Lease or CA Number	Inspection Item	Township	Range	Section	Quarter/Quarter	File Name
Production	4304730664	EL PASO PROD OIL & GAS CO	31-18 HALL ET AL	PGW	FEE	NRM1887	8S	22E	31	NWNW	NATL BUTE
Production	4304732716	EL PASO PROD OIL & GAS CO	FEDERAL 31-57	PGW	UTU43919	NRM1887	8S	22E	31	SENE	NATL BUTE
Production	4304733341	EL PASO PROD OIL & GAS CO	31-61	PGW	UTU43919	NRM1887	8S	22E	31	NENE	NATL BUTE
Production	4304733390	EL PASO PROD OIL & GAS CO	31-99	PGW	FEE	NRM1887	8S	22E	31	NENW	NATL BUTE
Production	4304733427	EL PASO PROD OIL & GAS CO	31-130	PGW	FEE	NRM1887	8S	22E	31	NWNE	NATL BUTE
		EL									

<u>Production</u>	<u>4304733428</u>	PASO PROD OIL & GAS CO	31-134	PGW	FEE	NRM1887	8S	22E	31	SWNW	NATL BUT
<u>Production</u>	<u>4304733438</u>	EL PASO PROD OIL & GAS CO	31-131	PGW	FEE	NRM1887	8S	22E	31	SWNE	NATL BUT
<u>Production</u>	<u>4304733439</u>	EL PASO PROD OIL & GAS CO	31-133	PGW	FEE	NRM1887	8S	22E	31	SENW	NATL BUT

DISCLAIMER for online data: No warranty is made by the BLM for use of the data for purposes not intended by the BLM.



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Washington, D.C. 20240

FEB 10 2003IN REPLY REFER TO:
Real Estate Services

**Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078**

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,**Director, Office of Trust Responsibilities****ACTING****Enclosure**

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

9 Greenway Plaza

CITY

Houston

STATE

TX

ZIP

77064-0995

PHONE NUMBER:

(832) 676-5933

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE	
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # _____

State Surety Bond No. RLB0005236

Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: 
Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.

NAME (PLEASE PRINT) David R. Dix

TITLE Agent and Attorney-in-Fact

SIGNATURE 

DATE 12/17/02

(This space for State use only)

Form 3160-5
(August 1999)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

SEE ATTACHED EXHIBIT "A"

9. API Well No.

SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	SUCCESSOR OF
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompletes horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and so forth following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed if testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

DIV. OF OIL, GAS & MINING

Approved by

THIS SPACE FOR FEDERAL OR STATE USE

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

OPERATOR CHANGE WORKSHEET

1. GLH

2. CDW

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **12-17-02**

FROM: (Old Operator):	TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY	WESTPORT OIL & GAS COMPANY LP
Address: 9 GREENWAY PLAZA	Address: P O BOX 1148
HOUSTON, TX 77064-0995	VERNAL, UT 84078
Phone: 1-(832)-676-5933	Phone: 1-(435)-781-7023
Account No. N1845	Account No. N2115

CA No.

Unit:

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
TRIBAL 31-98 (NRM-1887)	31-08S-22E	43-047-33375	12685	STATE	GW	P
HALL 31-99 (NRM-1887)	31-08S-22E	43-047-33390	12756	FEE	GW	P
TRIBAL 31-128	31-08S-22E	43-047-33460	12722	STATE	GW	P
TRIBAL 31-129	31-08S-22E	43-047-33461	12739	STATE	GW	P
HALL 31-130 (NRM-1887)	31-08S-22E	43-047-33427	12738	FEE	GW	P
HALL 31-131 (NRM-1887)	31-08S-22E	43-047-33438	12728	FEE	GW	P
TRIBAL 31-132	31-08S-22E	43-047-33462	12776	STATE	GW	P
HALL 31-133 (NRM-1887)	31-08S-22E	43-047-33439	12723	FEE	GW	P
HALL 31-134 (NRM-1887)	31-08S-22E	43-047-33428	12698	FEE	GW	P
HALL ETAL 31-18 (NRM-1887)	31-08S-22E	43-047-30664	95	FEE	GW	P
STATE 31 32	31-08S-22E	43-047-30906	175	STATE	GW	P
TRIBAL 31-62	31-08S-22E	43-047-33325	12575	INDIAN	GW	P
KENNEDY WASH 3-1	03-08S-23E	43-047-33663	12929	FEDERAL	GW	P
KENNEDY WASH 4-1	04-08S-23E	43-047-33664	99999	FEDERAL	GW	APD
KENNEDY WASH 6-1	06-08S-23E	43-047-33665	13047	FEDERAL	GW	PA
KENNEDY WASH 8-1	08-08S-23E	43-047-33614	12917	FEDERAL	GW	DRL
KENNEDY WASH 10-1	10-08S-23E	43-047-33919	99999	FEDERAL	GW	APD
KENNEDY WASH FED 11-1	11-08S-23E	43-047-33666	12988	FEDERAL	GW	P
KENNEDY WASH FED 13-2	13-08S-23E	43-047-33920	99999	FEDERAL	GW	APD
KENNEDY WASH FED 14-1	14-08S-23E	43-047-33667	13028	FEDERAL	GW	S

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
5. If **NO**, the operator was contacted contacted on: _____

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: 01/09/2003

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 03/26/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 03/26/2003

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238

2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ

2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

1/6/2006

FROM: (Old Operator):

N2115-Westport Oil & Gas Co., LP

1368 South 1200 East

Vernal, UT 84078

Phone: 1-(435) 781-7024

TO: (New Operator):

N2995-Kerr-McGee Oil & Gas Onshore, LP

1368 South 1200 East

Vernal, UT 84078

Phone: 1-(435) 781-7024

CA No.

Unit:

WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
-----------	-----	-----	-----	--------	-----------	------------	-----------	-------------

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- b. If **NO**, the operator was contacted on:
- a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on:

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 5/15/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
- Bond information entered in RBDMS on: 5/15/2006
- Fee/State wells attached to bond in RBDMS on: 5/16/2006
- Injection Projects to new operator in RBDMS on:
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: CO1203
- Indian well(s) covered by Bond Number: RLB0005239
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
The Division sent response by letter on:

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006. KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203

BIA BOND = RLB0005239

APPROVED 5/16/06

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technolcian

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Title

DRILLING MANAGER

Signature

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY L.P.

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandon <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
MAY 10 2006

DIV OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

BRAD LANEY

Signature

Title

ENGINEERING SPECIALIST

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Brad Laney

Title

Date

5-9-06

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)